Approved For Release 2000/08/28 : CIA-RDP78-04718A000100220077-4

PROPOSED PARKING AREA AND ACCESS R[illegible]

ACCESS ROAD

Excavation (Bulldozer) 400 cu. yds. @ .50	$ 200.00	
Base - 2-4" compacted layers of crushed stone or gravel 738 sq. yds. @ $1.85	1360.00	
Surface ½" Class A Surface Treatment Designation AT-50 492 sq. yds. @ .40	197.00	
Culverts 40' of 18" corrogated iron @ $.5.00 per lineal ft. in place	200.00	
Seeding 2220 sq. ft. @ $14 per 1,000 sq. ft.	31.00	
TOTAL ESTIMATE FOR ACCESS ROAD		$ 1,988.00

PARKING AREA

Excavation (including stockpiling topsoil) 8264 cu. yds. @ .30	$2480.00	
Pavement 3250 sq. yds. @ $2.25	7313.00	
Drainage Ditch 737 lineal feet @ .50	369.00	
Painting lines 3408 lineal feet @ .075	256.00	
TOTAL ESTIMATE FOR PARKING AREA		$10,418.00
GRAND TOTAL		$12,406.00
Plus 10% contingency		1,240.60
		$13,646.60

RECAP

Parking Area (117' x 250')	$10,418.00
Access Road (370' long x 12' wide)	1,988.00
Real Estate & Construction (Add. for rock & contingency)	2,844.00
TOTAL	$15,250.00

Approved For Release 2000/08/28 : CIA-RDP78-04718A000100220077-4